Project planning report

Saved project inputs and selected calculation results

2026-11-11 06:49:11.536953+00:00

Project

This report presents saved project inputs and the original results of the selected calculations. Country-specific requirements, electrical design and installation checks remain open. It does not approve the complete installation.

Project	Commercial · 100 kWp · E2E-PDF-PROBE 80331
Project reference	c5fac5b61d2f499cb60f8550a42c1a6f
Input revision	2

Site and project inputs

Location	E2E-PDF-PROBE 80331
Country	—
Time zone	—
Project note	Planned orientation: South-facing, 30°

Equipment checks

Country requirements are not assessed by the selected calculations.

Assessment status	Requirements not met

Converter output

Assessment status	Checked requirements met
Result	25 kW
Source document · Page 2	25000 W https://de-linker.com/wp-content/uploads/2026/09/H2-10-30K-T2T3-datasheet-EN-BEU.pdf

Grid phases

Assessment status	Checked requirements met
Result	3
Requirement	3

PV input power

Assessment status	Requirements not met
Result	45 kWp
Requirement	100 kWp
Source document · Page 2	45000 Wp https://de-linker.com/wp-content/uploads/2026/09/H2-10-30K-T2T3-datasheet-EN-BEU.pdf

PV strings and inputs

Assessment status	Checked requirements met
Result	3
Source document · Page 2	3 https://de-linker.com/wp-content/uploads/2026/09/H2-10-30K-T2T3-datasheet-EN-BEU.pdf

Required accessory

Assessment status	Checked requirements met
Result	SAJ BC2-HV1

Manufacturer pairing

Assessment status	Checked requirements met
Source document	https://de-linker.com/wp-content/uploads/2026/09/H2_HS2_HS3_AS2_AS3_Configuration_Instructions_V1.0_en.pdf https://de-linker.com/wp-content/uploads/2026/09/H2_HS2_HS3_AS2_AS3_Configuration_Instructions_V1.0_en.pdf
Source document	https://de-linker.com/wp-content/uploads/2026/10/B2-5.0-HV1-HV5-user-manual-EN-EU.pdf https://de-linker.com/wp-content/uploads/2026/10/B2-5.0-HV1-HV5-user-manual-EN-EU.pdf
Source document · Page 2	https://de-linker.com/wp-content/uploads/2026/09/B2-5-25K-HV1HV5-datasheet-EN-BEU.pdf https://de-linker.com/wp-content/uploads/2026/09/B2-5-25K-HV1HV5-datasheet-EN-BEU.pdf
Source document · Page 37	https://de-linker.com/wp-content/uploads/2026/10/SAJ_H2_10-30K_User-Manual_DE-EN_EU.pdf https://de-linker.com/wp-content/uploads/2026/10/SAJ_H2_10-30K_User-Manual_DE-EN_EU.pdf

Module count

Assessment status	Checked requirements met
Result	2
Requirement	2 – 2
Source document · Page 2	2 https://de-linker.com/wp-content/uploads/2026/09/B2-5.0-25.0-HV1HV5_datasheet_en_AU.pdf

Parallel arrangement

Assessment status	Checked requirements met
Result	1

Battery voltage

Assessment status	Further checks required
Source document · Page 2	180~800 V https://de-linker.com/wp-content/uploads/2026/09/H2-10-30K-T2T3-datasheet-EN-BEU.pdf
Source document · Page 2	89.6-115.2 / 179.2-230.4 / 268.8-345.6 / 358.4-460.8 / 448-576.0 V https://de-linker.com/wp-content/uploads/2026/09/B2-5-25K-HV1HV5-datasheet-EN-BEU.pdf

Sales unit

Assessment status	Checked requirements met
Source document · Page 2	Battery system https://de-linker.com/wp-content/uploads/2026/09/B2-5-25K-HV1HV5-datasheet-EN-BEU.pdf

Usable energy

Assessment status	Further checks required
Requirement	342.5 kWh
Source document · Page 2	9.0 kWh https://de-linker.com/wp-content/uploads/2026/09/B2-5-25K-HV1HV5-datasheet-EN-BEU.pdf

Continuous AC discharge power

Assessment status	Requirements not met
Result	25 kW
Requirement	60 kW
Source document · Page 2	25000 W https://de-linker.com/wp-content/uploads/2026/09/H2-10-30K-T2T3-datasheet-EN-BEU.pdf

Battery discharge path

Assessment status	Further checks required

Backup transfer

Assessment status	Further checks required

Components and manufacturer conditions

The H2 T3 ships with a smart meter, three current transformers and a 10 m meter communication cable (H2 manual, section 2.2 Unpacking, PDF p. 36 English / p. 7 German).

SAJ's B2 datasheet names B2-5.0 to B2-25.0 as one to five BU2-5.0 modules with one BC2-HV1 control module, and the B2 manual (V1.2, PDF p5) says the B2 can only be used as such a set: the control module is an article of its own.

SAJ's Configuration Instructions V1.0 (Section 2) give the H2 series system as H2 + BC2 + BU2. SAJ's B2 datasheet names B2-5.0 to B2-25.0 as one to five BU2-5.0 modules with one BC2-HV1 control module, and SAJ's B2 manual (V1.2, PDF p5) says the B2 can only be used as a set with SAJ's H2 high voltage series storage inverter. The listing does not cover the one-module B2-5.0, whose operating voltage lies below the H2 T3's battery voltage range.

SAJ's B2 datasheet gives 179.2 to 230.4 V for the two-module B2-10.0; the H2 T3 manual's battery voltage range begins at 180 V.

Source document · Page 36	https://de-linker.com/wp-content/uploads/2026/10/SAJ_H2_10-30K_User-Manual_DE-EN_EU.pdf https://de-linker.com/wp-content/uploads/2026/10/SAJ_H2_10-30K_User-Manual_DE-EN_EU.pdf
Source document	https://de-linker.com/wp-content/uploads/2026/09/H2_HS2_HS3_AS2_AS3_Configuration_Instructions_V1.0_en.pdf https://de-linker.com/wp-content/uploads/2026/09/H2_HS2_HS3_AS2_AS3_Configuration_Instructions_V1.0_en.pdf
Source document	https://de-linker.com/wp-content/uploads/2026/10/B2-5.0-HV1-HV5-user-manual-EN-EU.pdf https://de-linker.com/wp-content/uploads/2026/10/B2-5.0-HV1-HV5-user-manual-EN-EU.pdf

Source document · Page 2	https://de-linker.com/wp-content/uploads/2026/09/B2-5-25K-HV1HV5-datasheet-EN-BEU.pdf https://de-linker.com/wp-content/uploads/2026/09/B2-5-25K-HV1HV5-datasheet-EN-BEU.pdf
Source document · Page 37	https://de-linker.com/wp-content/uploads/2026/10/SAJ_H2_10-30K_User-Manual_DE-EN_EU.pdf https://de-linker.com/wp-content/uploads/2026/10/SAJ_H2_10-30K_User-Manual_DE-EN_EU.pdf

Provisional bill of materials

This table lists selected equipment, saved roof modules, manufacturer-included components, customer-supplied requirements and site-engineering obligations. Quantities are shown only where established. It is not a complete balance-of-system take-off; mounting, cabling, protection and other installation materials still require project-specific design.

Source document · Page 43 — Installation requirement source
https://de-linker.com/wp-content/uploads/2026/10/SAJ_H2_10-30K_User-Manual_DE-EN_EU.pdf

Quantity	Product	Reference	Supply scope
1 pc	SAJ H2-25K-T3	DLK-SAJ-H225KT3	Selected equipment
—	MPPT PV input terminals	p. 43 · B MPPT1 PV input C MPPT2 PV input For safety operation and regulation compliance, install air circuit breaker between the grid and the inverter. D MPPT3 PV input	Site engineering assessment required
—	Battery input terminals (BAT1/BAT2)	p. 43 · E BAT1+, BAT1- Battery input H2-(10K-20K)-(T2,T3) 50A F BAT2+, BAT2- Battery input	Site engineering assessment required
—	Communication terminal	p. 43 · I LAN/ CAN/ PART/ EMS/ RS485/ Communication port By installing a circuit breaker, the inverter can be disconnected from the grid quickly and safely when the METER/ DRMs	Site engineering assessment required
—	Grid and back-up terminals	p. 43 · J BACK-UP Backup loads K GRID Grid	Site engineering assessment required
—	Grounding terminal	p. 43 · G Grounding	Site engineering assessment required
1 pc	SAJ BC2-HV1	DLK-SAJ-BC2HV1	Selected equipment
1 pc	SAJ B2-10.0-HV1	DLK-SAJ-B2100HV1	Selected equipment
—	Energy meter		Included according to manufacturer · quantity unconfirmed

Saved calculation references

Calculation reference	67008ee795d14360845e85c64e571f50 · Input revision 1 · d035906ecca6fcfd3d8680c671f8c2954cdac742ef20489564e28a771c4371fa

Certificates and related product documents

These documents were linked to the selected products when this result was recorded. Their applicability to this project’s models, firmware, configuration, standard editions and annexes has not been assessed here. Compliance with country-specific requirements, installation approval and grid-operator acceptance require separate evidence.

H2-25K-T3	EU declaration of conformity for the SAJ H2 inverters, 13 languages including English and German (names the H2-25K-T3) https://de-linker.com/wp-content/uploads/2026/10/SAJ_H2_EU-Declaration-of-Conformity.pdf?linker_document_sha256=9881d06dabba6e53893923e93ebb90365b966429967104cb92890de39573b443
SHA-256	9881d06dabba6e53893923e93ebb90365b966429967104cb92890de39573b443
Recorded document revision	fb5225d28630fe44b0f7bb73ba5097e91063d5281bbdbdae5a4449031da639cc
B2-10.0-HV1 · BC2-HV1	SAJ B2 battery systems and BC2-HV1 control module: EU declaration of conformity (multilingual) https://de-linker.com/wp-content/uploads/2026/10/SAJ_B2_BC2-HV1_EU-Declaration-of-Conformity.pdf?linker_document_sha256=9cb10f8699f660cbbde4197f30b392b8b7b77d95723a8a0ad4c18a416b854a61
SHA-256	9cb10f8699f660cbbde4197f30b392b8b7b77d95723a8a0ad4c18a416b854a61
Recorded document revision	0031f8b51adbabce170b079ddb5dfe0a6133364939b1c379daa16f20b14ba565
B2-10.0-HV1	SAJ B2 battery systems and BU2-5.0 battery modules: EU declaration of conformity (multilingual) https://de-linker.com/wp-content/uploads/2026/10/SAJ_B2_BU2-5.0_EU-Declaration-of-Conformity.pdf?linker_document_sha256=6a45702bfe4ae9de06c173b084b3decbf6ac9cc3cc5f77cbe0f8686885c9ad6e
SHA-256	6a45702bfe4ae9de06c173b084b3decbf6ac9cc3cc5f77cbe0f8686885c9ad6e
Recorded document revision	96afb3f9ec952bbdf56d5a7ad8f2b4b89a1deca2d342615847aaf5c908b68f32